KOLAR DIVISION.

Dated 11th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 27th October 1930, for Restoring Paravanahalli Hulikere, Bowringpet Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimates and the conditions may be seen at the Executive Engineer's Office, at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Paravanahalli Hulikere, of Bowringpet Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderer must quote specific rates for all items of work both in words and in figures.

10. Tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for Restoring Paravanahalli Hulikere of Bowringpet Taluk.

Serial No.	Items of work	Unit	Rates	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork to bund with watering and tamping with lead and lift.	C.yd.		3,910	
2	Earthwork to bund to breach with 3" layer and watering, tamping, etc.	,,		436	
3	Turfing to bund	Sq.yd.		2,477	
4	Removing and resetting old stone work with new jelly.	C.yd.		245	
5	New stone work with jelly	,,		679	
6	Providing new grade stones with numbering and painting.	Each		11	
7	Do do index stones ..	,,		11	
8	Do Register No. stones ..	,,		1	
9	Bench mark stones	,,		2	
10	Gauge stones	,,		1	
11	Jungle clearing and removing *prickly pears* and lantanas, cutting trees and removing roots and ant hills.	Grade		9	
12	Earthwork excavation for puddle wall ...	C.yd.		15	
13	Puddle wall with good clay	,,		62	
	Total Bund ...	...	...	...	...

No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice.		Rs. a. p.		Rs.
1	Earthwork Excavation ...	C.yd.		42	
2	Refilling with watering and tamping ...	"		27	
3	Surki concrete with burnt stone jelly ...	C.ft.		303	
4	Burnt brick in surki mortar	"		178	
5	Burnt stone slabs ...	S.ft.		195	
6	Plastering with surki morter	Sqr.		3·82	
7	Providing wooden plug and iron rod and locking arrangement.	Lump	sum	Rupees	
8	Cutting holes in cross orifice slabs ...	"	"	"	
	Total Sluice ...	...	...	...	...
	Sluice No. 2 as per Sluice No. 1 Wasteweir.				
1	Earthwork excavation in hard soil and using the same to bund.	C.yd.		78	
2	Surki concrete	C.ft.		179	
3	Burnt brick in surki mortar			452	
4	Burnt stone slabs 6" thick	Sq.ft.		265	
5	Plastering with surki mortar ...	Sqr.		6·41	
6	Rough stone work for apron ...	C.yd.		64	
7	Site clearing	Lump	sum	Rupees	
	Total Weir ...	...	...	....	....
	Total bund sluice and weir ...	...	...	...	...
	Contingencies ...	...	...	....	...
	Grand Total ...	...	...	...	...

Dated 11th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 27th October 1930, for Restoring Kurubarahalli Tippakunte Register No. 623—819, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Kurubarahalli Tippakunte, Kolar Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderer must quote specific rates for all items both in words and in figures.

10. Tenders stating that the work would be executed at certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for Restoring Kurubarahalli Tippasunte Register No. 623—819, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
					Rs.
1	Earthwork to bund with watering and tamping with lead and lift, etc., complete.	C.yd.	Rs.	4,780	
2	Tusfing.	Sq.yd.		3,759	
3	Removing and resetting old stone work with new jelly.	C.yd.		188	
4	New stone work with jelly	,,		557	
5	Providing and fixing new grade stone with numbering painting.	Each		16	
6	Do do do ..	,,		16	
7	Do gauge stones	,,		1	
8	Do Registered No. stones ...	,,		1	
9	Bench mark stones	,,		2	
10	Cutting jungle and removing ant hills	Lump	sum		
	Total Bund ...	..	..	...	..
	Sluice.				
1	Earthwork excavation	C.yd.		39	
2	Refilling the same with watering and tamping ...	,,		39	
3	Surki concrete	C.ft.		335	
4	Burnt brick in surki mortar	,,		161	
5	Burnt stone slabs 4" to 6"	Sq.ft.		159	
6	Plastering with surki mortar	,,		3·96	
7	Providing wooden and plug and rod with locking arrangements.	Lump	sum		
8	Cutting holes in cross and orifice slabs	Each		2	
	Total Sluice ...	...	..	...	...
	Waste weir.				
1	Earthwork excavation	C.yd.		75	
2	Surki concrete	C.ft.		249	
3	Burnt brick in surki mortar	,,		543	
4	Burnt stone slabs 4" to 6"	Sq ft.		304	
5	Plastering with surki mortar	Sqr.		5·42	
6	Rough stone work new	C.yd.		71	
	Total Weir ...	...	...	...	...
	Total of Bund, Sluice and Weir ...	...	...	...	..
	Contingencies ...	..	...	...	...
	Grand Total Rupees ...	..	...	...	...

N. LAKSHMINARSIMIAH,
Executive Engineer.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Abstract Notification.

Attention of the public is hereby invited to the detailed Notification, dated 27th September 1930, calling for tenders for constructing electrical buildings at Chikballapur Town and for constructing a block of two Operators' quarters at Dodballapur, published in Part VI, pages 1224 to 1225 of the *Mysore Gazette*, dated 9th October 1930. The latest date for receiving tenders is 2 P.M., on 31st October 1930.

Abstract Notification.

Attention of the public is hereby invited to the detailed Notification, dated 19th September 1930, calling for tenders for constructing a Block of Operators' Quarters with a unit of latrine at Tumkur Town, published in Part VI, pages 1223 to 1224 of the *Mysore Gazette*, dated 9th October 1930. The least date for receiving tenders is 2 P.M., on the 27th October 1930.

C. M. CARIAPA,
Chief Electrical Engineer.